BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2023-24/OW/WORK_INDENT2534

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/16/2023-24, Date: 02-02-2024

Name Of Work: Maintenance of water supply works to existing borewells at Kattigenahalli, Bellahalli, Thirumenahalli, Chokkanahalli surrounding area in ward no. 05 (Kogilu).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHASHANK K	
				In Figures	In Words
1	20.00	The lifting of submergible pumpset from well. Water Supply and UGD Works	Each	229.00	Rupees Two Hundred Twenty Nine Only
2	20.00	The Transportation of pumping machineries Water Supply and UGD Works	Each	1100.00	Rupees One Thousand One Hundred Only
3	4.00	Rewinding of submergible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submergible pumpsets etc.(with guarantee period not less than 6 months) for Water Supply and UGD Works For all types of submergible pumpsets above 7.0 HP and upto 7.5H.P.	Each	3000.00	Rupees Three Thousand Only
4	6.00	For all types of submergible pumpsets above 10 HP and upto 11 H.P.	Each	4500.00	Rupees Four Thousand Five Hundred Only
5	5.00	For all types of submergible pumpsets above 12 HP and upto 13 H.P.	Each	5000.00	Rupees Five Thousand Only
6	5.00	For all types of submergible pumpsets 15HP to 20 HP	Each	8000.00	Rupees Eight Thousand Only
7	20.00	Pump bowls of same type and make Water Supply and UGD Works CSR 2023-24 V-5	Each	1350.00	Rupees One Thousand Three Hundred Fifty Only
8	20.00	Intermediate Piece (I.P) With IP Leaded Bronxe bush Water Supply and UGD Works CSR 2023-24 V-5	Each	900.00	Rupees Nine Hundred Only
9	20.00	Upper Flange Water Supply and UGD Works.	Each	550.00	Rupees Five Hundred Fifty Only
10	20.00	Upper/ Lower Housing Water Supply and UGD Works.	Each	1100.00	Rupees One Thousand One Hundred Only
11	20.00	Guide vane Water Supply and UGD Works.	Each	700.00	Rupees Seven Hundred Only
12	20.00	Impeller Shell moulded with aluminium Bronze) Water Supply and UGD Works .	Each	1300.00	Rupees One Thousand Three Hundred Only
13	20.00	Discharge outlet (D.O) Bearing D.O Steel Bush Water Supply and UGD Works .	Each	1900.00	Rupees One Thousand Nine Hundred Only
14	20.00	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) Water Supply and UGD Works .	Each	1300.00	Rupees One Thousand Three Hundred Only
15	20.00	Pump Couping (Stainless Steel) Water Supply and UGD Works .	Each	1300.00	Rupees One Thousand Three Hundred Only
16	50.00	Stud and Nuts Water Supply and UGD Works	Each	180.00	Rupees One Hundred Eighty Only
17	20.00	Motor Base With Pin Water Supply and UGD Works	Each	450.00	Rupees Four Hundred Fifty Only
18	20.00	The Starter of Motor up to 4 to 5 HP Water Supply and UGD Works.	Each	3250.00	Rupees Three Thousand Two Hundred Fifty Only
19	20.00	The Rotor of Motor up to 4 to 5 HP Water Supply and UGD Works.	Each	1750.00	Rupees One Thousand Seven Hundred Fifty Only
20	20.00	Carbon Housing Water Supply and UGD Works .	Each	1750.00	Rupees One Thousand Seven Hundred Fifty Only
21	20.00	Thrust bearing block assembly complete with Segment bearing pad.up to 4 to 5 HP Water Supply and UGD Works.	Each	1750.00	Rupees One Thousand Seven Hundred Fifty Only
22	20.00	Oil Seal Water Supply and UGD Works	Each	350.00	Rupees Three Hundred Fifty Only
23	20.00	Oil Seal Steel BushWater Supply and UGD Works .	Each	250.00	Rupees Two Hundred Fifty Only
24	65.00	Steel Bush Water Supply and UGD Works .	Each	400.00	Rupees Four Hundred Only
25	65.00	Allen Screw Water Supply and UGD Works .	Each	1200.00	Rupees One Thousand Two Hundred Only
26	20.00	Pump Key (Stainless Steel) Water Supply and UGD Works.	Each	650.00	Rupees Six Hundred Fifty Only

Shashank K
Signature of Contractor

Executive Engineer

Name Of Work: Maintenance of water supply works to existing borewells at Kattigenahalli, Bellahalli, Thirumenahalli, Chokkanahalli surrounding area in ward no. 05 (Kogilu).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHASHANK K	
				In Figures	In Words
27	10.00	Non return valve (NRV) assembly complete with rubber 'O'Ring Water Supply and UGD Works.	Each	650.00	Rupees Six Hundred Fifty Only
28	20.00	Cable Guard Water Supply and UGD Works .	Each	350.00	Rupees Three Hundred Fifty Only
29	20.00	Strainer Water Supply and UGD Works	Each	450.00	Rupees Four Hundred Fifty Only
30	20.00	Brass Filter Water Supply and UGD Works	Each	1050.00	Rupees One Thousand Fifty Only
31	20.00	Re-erection charges of pumping machineries including overhauling and pointing Water Supply and UGD Works	Each	2000.00	Rupees Two Thousand Only
32	20.00	Lock Ring Water Supply and UGD Works	Each	350.00	Rupees Three Hundred Fifty Only
33	20.00	Top Carbon/Ferrodo padding Water Supply and UGD Works	Each	350.00	Rupees Three Hundred Fifty Only
34	20.00	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush Water Supply and UGD Works	Each	850.00	Rupees Eight Hundred Fifty Only
35	20.00	Circillps Water Supply and UGD Works	Each	200.00	Rupees Two Hundred Only
36	54.00	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.63 Amps	No.	401.00	Rupees Four Hundred One Only
37	270.00	Cutting and threading G.I. pipes for pump fitting, public fountains with appurtenances., where the length of pipe laid is less than 6 metre Pipes of dia 32mm to 80mm Water Supply and UGD Works	Each	322.00	Rupees Three Hundred Twenty Two Only
38	1100.00	Supply and delivery at site Brand new best make PVC insulated cable of Flat 3 core (sheathed) of nominal cross sectional area as per IS 694-1990 with ISI Mark and as per its latest amendments. 1x3x6 m2 Water Supply and UGD Works	Mtr	185.00	Rupees One Hundred Eighty Five Only
39	20.00	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box. Water Supply and UGD Works .	No	1265.00	Rupees One Thousand Two Hundred Sixty Five Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike